

# Operating manual

- GB -

Hot Water - High-pressure cleaners

Therm C

11/130 13/180 15/150



Read and conform safety instructions before use! Keep instructions in a safe place for later use and pass them on to any future user.







### **Dear Customer**

We would like to congratulate you on your new hot water high pressure cleaner, and to thank you for buying it!

The following pages contain information about the machine in order to familiarize you with it and facilitate its use.

The machine is a professional cleaning aid in all cleaning tasks, e.g.:

- facades - vehicles of all types - containers


- flagstones - sheds e.g.: food processing

- removing of old paint etc. - machines industry

| Technical data                         | therm C 11/130         | therm C 13/180         | therm C 15/150         |
|--|------------------------|------------------------|------------------------|
| Operating pressure                     | 30 - 130 bar           | 30 - 180 bar           | 30 - 150 bar           |
| Nozzle size                            | 25045                  | 25045                  | 25055                  |
| Permissible overpressure               | 145 bar                | 200 bar                | 170 bar                |
| Water output (*1)                      | max. 660 l/h           | max. 780 l/h           | max. 900 l/h           |
| Hot water output                       | 12 - 80 °C             | 12 - 80 °C             | 12 - 80 °C             |
| Steam level                            | max. 140 °C            | max. 140 °C            | max. 140 °C            |
| Heat.oil nozzle/Heat.oil press.        | 1.35 Gph/10bar         | 1.5 Gph/10bar          | 1.5 Gph/10bar          |
| · '                                    | •                      | ·                      | •                      |
| Heat. oil consumpt. (Heat. oil EL)     | 4.8 kg/h (=5.7<br>l/h) | 5.7 kg/h (=6.8<br>l/h) | 6.3 kg/h (=7.5<br>l/h) |
| Heating capacity                       | 50 kW                  | 60 kW                  | 67 kW                  |
| Exhaust gas mass flow                  | 0.032 kg/s             | 0.035 kg/s             | 0.041 kg/s             |
| Fuel tank                              | 25 I                   | 25 I                   | 25 I                   |
| High pressure hose                     | 10 m                   | 10 m                   | 10 m                   |
| with hose drum                         | 15 m                   | 15 m                   | 15 m                   |
| Electrical rating:                     | 230V / 50Hz / 15A      | 400V / 50Hz / 8.7A     |                        |
| Input                                  | P1: 3.4 kW             | P1: 4.8 kW             | P1: 4.8 kW             |
| Output                                 | P2: 2.3 kW             | P2: 4.0 kW             | P2: 4.0 kW             |
| Weight                                 | 150 kg                 | 150 kg                 | 150 kg                 |
| Dimens. in mm without reel             | 790 x 590 x 980        | 790 x 590 x 980        | 790 x 590 x 980        |
| Sound level                            | 88 dB                  | 89 dB                  | 89 dB                  |
| Guaranteed sound level L <sub>wA</sub> | 90 dB                  | 93 dB                  | 92 dB                  |
| Vibrations at lance                    | 2.1 m/s <sup>2</sup>   | 2.1 m/s <sup>2</sup>   | 2.2 m/s <sup>2</sup>   |
| Recoil at lance                        | approx. 20 N           | approx. 22 N           | approx. 24 N           |

Permissible tolerance for figures ± 5 % in acc. with VDMA uniform sheet 24411

**Connections and functional parts** 



- 1 Water inlet connection with filter
- 2 Power cable
- 3 Winder for cable
- 4 Suction hose for detergent
- 5 High pressure hose
- 6 Spray gun

- 8 Storage bin for spray gun and pipe
- 9 Brake
- 10 Fuel tank
- 11 Filler aperture for fuel
- 12 High pressure outlet
- 13 Hose drum (special accessories)



- 15 Master switch (appliance On- Off)
- 16 (Burner ON- OFF) ignition
- 17 Brief operating instructions
- 18 Manometer
- 19 Thermostat
- 20 Detergent dispensing valve

### Water system

The water flows into a tank.

A float valve (a) regulates the water intake.

The water is then directed to the safety spray pipe under pressure from the high pressure pump.

The high pressure spray is formed through the nozzle on the spray pipe.



### **Detergent and caring system**

The high pressure pump can also suck a detergent/caring agent and mix it with the high pressure jet. - The detergent must have the ph-value 7-9 neutral.



Only open the dosing valve, if the chemistry sieve is placed in a liquid.

The rules concerning the environment, refuse and ground water protection must be complied with!

### Pressure control and safety facilities

The pressure control valve allows full adjustment of the quantity and pressure of the water.

The safety valve protects the machine from excessive pressure and cannot be adjusted beyond the admissible operating pressure. The setting nuts are sealed with lacquer.



### **■** Excess temperature release

As an additional safety device the appliance is equipped with an excess temperature sensor inside the chimney. Should the safety devices as e.g. the float monitoring device be defectice and the burner continues to heat although the heating coil does not conduct away heat a destruction of the heating coil would be inevitable. As soon as the temperature inside the chimney exceeds 260 °C the excess temperature release triggers and cuts out the appliance.

The display of the excess temperature release is located on the back of the switchbox inside the appliance.



**RED**: Excess temperature released, let appliance cool down, no hot water operation possible

YELLOW: Appliance cooled down, activation of hot water opertion possible by pressing the RESET-button

ATTENTION !!!

Immediately contact service in case of recurrence



Replacements, repairs, new adjustments and sealing operations may only be performed by trained personnel.

### **Motor protection switch**

The pump motor is protected from overload by a motor protecting switch. In case of an overload the motor is switched off by this motor protecting switch. For a restart the master switch has to be switched off and then on again. In case of a repeated switching off of the motor by the motor protecting switch the cause of the malfunction has to be removed.



Replacement and inspection work may only be performed by trained personnel.

### Spray pipe with spray gun

The spray gun only allows the machine to be operated when the safety trigger is pulled.

The spray gun can be used when the safety trigger is pulled. The liquid is then pumped up to the nozzle. Spray pressure builds up and quickly reaches the selected operating pressure.



When the trigger is released the gun is closed, which prevents any further liquid from coming out of the spray pipe.

The recoil resulting from the gun being closed opens the pressure control valve in the machine. The pump remains switched on and pumps the circuit with reduced overpressure. When the gun is opened the pressure control valve closes and the pump starts to operate again at the selected pressure.

If the spray gun is closed for more than 20 seconds the motor switches off. The motor restarts as soon as the safety trigger is pulled again.

If the gun is closed for more than 20 minutes, the safety switch-off is activated and the high-pressure cleaner switches off completely, i.e. to be able to work with your cleaner it has to be switched OFF and then ON again with the master switch.

After completing work with your **Kränzle therm C**, or if work is interrupted, the safety catch (1) must be applied. This makes it impossible to press the trigger by accident.





The spray gun is a safety device. Repairs may only be performed by trained personnel. If spare parts are required, use only those approved by the maker.

### **Thermostat**

The thermostat with rotary control switch controls the temperature of the spray water.

Use the rotary control switch to adjust the desired water temperature.



Thermostat with rotary control switch

### High pressure hose and spray equipment

The high pressure hose and spray equipment supplied with the machine are made of high quality material specially adapted for the operating conditions of the machine, and are properly marked.



If spare parts are required, only properly marked components approved by the maker should be used. High pressure hoses and spray equipment must be connected so that they are pressure-tight. The high pressure hoses should not be driven over, pulled excessively or twisted. Do not pull the hose over sharp edges, since this will invalidate the warranty.

### **Heat exchanger**

Heating coil: 34 m long - Content: 5 l of water - Heating capacity: 70 k W

The heat exchanger is heated by a high pressure fan heater.


A ventilator (1) draws in the cold, fresh air from the bottom end of the machine and forces it upwards between the outer mantle (2) and the inner mantle (3). In the process, the fresh air is pre-heated and the outer mantle of the heat exchanger is cooled.

The pre-heated air is pressed through a mixing unit (4). Here finely atomized fuel is injected via a nozzle (5) and mixed with the air. The electrodes (6) located below then ignite the fuel-air mixture.

The flame burns from top to bottom, turns round and the hot gas flows past the heating coil (7) on its way back up. The burned gases collect in the exhaust chamber and are emitted from the chimney (8).

The water is forced through a heating coil by the high pressure pump. Hot air flows around the coil, as described above.

The fuel pump (9) draws the oil through a filter (10) and pumps it to the injector nozzle (5). The surplus quantity of fuel flows straight back into the tank. The oil pressure is shown on the fuel manometer (11).



# Safety Information

### **Brake**

The Kränzle therm is fitted with a brake that prevents the machine from rolling away on flat ground.

Always apply the brakes firmly when working with the machine !!!



**Brake applied** 



Brake not applied

If you want to move the high pressure cleaner into another direction, first slightly tilt back the machine by pressing the foot rest and pulling the pushbar at the same time.



Now you can move the cleaner into the desired direction.

### **Safety Information**



#### **CAUTION !!!**

For safety reasons always put the master switch into the "0" position (=power switch-off) after completion of work.

When starting the cleaning process do not aim the high pressure jet at the object to be cleaned for at least 30 seconds.

It is possible, that the water contents in the combustion chamber (approx. 5 litres) has changed colour due to the resting time.

# Safety Information

### **Safety Information**

#### **IMPORTANT!!!**



The machine must be disconnected from the power supply when servicing work is being carried out. The master switch should be in position "0" and the plug out of the socket.


Do not use the cleaner if electrical connections or other safety-relevant parts (e.g. overpressure valve, high pressure hose, spraying equipment etc.) are damaged.

The machine may only be used by persons who have received the necessary training.

- Never operate the machine without supervision.
- The water spray can be dangerous. It should never be directed at people, animals, electrical apparatus or the machine itself.
- Never direct the spray at power sockets.
- Parts of the machine interior and parts of the gun and lance become hot when hot
  water is used. Leave the cover of the machine closed when using the machine and do
  not touch the metallic parts of the gun and lance.
- Children must not use high pressure cleaning equipment.
- Do not damage the cable or repair it incorrectly.
- Do not pull the high pressure hose if there are kinks or loops in it. Make sure that the hose is not damaged on sharp edges.
- Persons operating the machine should wear the necessary protective clothing, i.e., waterproof clothing, rubber boots, safety goggles, headwear etc. It is prohibited to use the machine in close vicinity to people lacking suitable protective clothing.
- The high pressure spray can generate a high level of noise. If noise exceeds the maximum allowed levels, users and others in the vicinity must wear suitable ear protection.
- The high pressure spray causes recoil and additional twisting movement if the gun is angled.
   The gun must therefore be held firmly with both hands. (see page 2)
- Do not close off the exhaust aperture on the topside of the machine. Do not bend over this aperture and do not put your hands inside it. Exhaust gases are very hot!
- Do not clamp down the trigger of the gun. Apply the safety catch after use, in order to prevent accidental spraying.
- Do not spray against matter containing asbestos or other hazardous substances.
- Never spray liquids containing solvents, such as paint thinner, petrol, oil, or anything similar. Note the specifications of the additive makers! The seals in the machine are not resistant to solvents. The spray vapour of solvents is highly inflammable, explosive and poisonous.


# Safety Information

- The machine may not be set up and used in rooms where there is a danger of fire or explosion. The machine may not be used under water.
- Air is required for combustion, and exhaust fumes are generated. If the machine is used in closed rooms, make sure that the exhaust fumes can escape and that there is adequate ventilation.
- Use light heating oil EL (DIN 51 603) or Diesel (DIN EN 590) only. The use of other fuel is perilous and may even cause an explosion.
- Never direct the high-pressure jet at yourself or other persons just to clean clothing or shoes.





As to the recoil see notice on page 2!

Apply the safety catch on the spray gun after each use, in order to prevent unintentional spraying!



# This is prohibited!







Never pull the high pressure hose if it has formed kinks or "nooses"! **Never pull the hose** over sharp edges!

# This is prohibited!






Never allow children to use the high pressure cleaner!



Never direct the water jet at the machine itself!



Never direct the water jet at a power socket!

### Commissioning

- Secure the machine by applying the brake (see page 8)
- and check the oil level of the high pressure pump.

Do not start the machine if there is no oil on the dipstick. Fill oil if necessary. See page 18.



Fill the fuel tank with light heating oil prior to use.



Use EL heating oil (DIN 51603) or Diesel fuel only. Unsuitable fuels, such as petrol, may not be used (danger of explosion).

### **Electrical connection**

Make sure that the master switch is switched off (position "0").

Plug in the power cable of your high-pressure cleaner.

The voltage given on the specification plate must match the mains voltage. You can find the specification plate on the front right-hand side of the appliance.



The machine is supplied with a power cable and plug.

The plug must be connected to a properly installed electrical socket with earthing and have a 30 mA FI residual current circuit breaker. The socket must have a neutral 16A fuse on the mains side.

If an extension cable is used, it must have an earth line that is properly connected to the plug connections. The lines in the extension cable must have a cross section of at least 1.5 mm<sup>2</sup>. The plug connections must be of spray protected design and may not lie on a wet surface. (If the extension cable is longer than 10 m the minimum cross section is 2.5 mm<sup>2</sup>)

### Important!



Extension cables that are too long cause a drop in the voltage and thus interruptions in operation. If you are using a cable drum, the cable must always be fully unwound.

### **High pressure connection**

Connect the high pressure hose to the handgun.

Unwind the hose so that it is free of loops and connect it to the handgun and the machine.



Check that all screw-type connections are pressure-tight. Leaks from gun, high pressure hose or hose drum must be eliminated immediately. Leakage leads to increased wear.

### Water connection

Connect the machine to a water tap using a hose of at least 1/2" and turn on the tap. (2-10 bar admission pressure)

The water tank in the machine fills up. When the tank is full, the built-in float valve closes the water inlet.

Use clean water only!

### **CAUTION!**

Please pay attention to the regulations of your waterworks company.

In accordance with EN 61 770, the machine may not be directly connected to the public drinking water supply lines.

A brief connection however is permissible according to DVGW (German Association for Gas and Water Affairs) if a tube ventilator with check valve (Kränzle Order-No. 41.016 4) is built into the water supply.

Also indirect connection to the public drinking water supply lines is permissible by way of free emission in accordance with EN 61 770; e.g. by using a reservoir with a float valve.

Direct connection to a non-drinking water supply line is permissible.

### Switch-on



- Switch off the ignition. Rocker switch (16) to "0".
- Set the pressure control (4) valve to maximum pressure (see below) and close the detergent valve (20).
- Open the gun and switch the master switch (15) on.

The high pressure pump now presses the air out of the lines, and after a short time the high pressure spray is formed and the operating pressure is reached. If the system has to be deaerated (appliance rattles), open and close the spray gun repeatedly.





### **CAUTION**

After an extended standstill do not instantly aim the high pressure water jet at the object to be cleaned, as the remaining water inside the high pressure cleaner may be discoloured.

### Adjusting the pressure

Use the pressure control valve (4) directly on the pump head to adjust the pressure.



turn right: max.



The machine is fitted with a Total-Stop-System. If the gun is closed for longer than approx. 20 seconds, the machine switches off automatically, after 20 minutes the machine moves to safety switch off and you must use the master switch to turn it back on. The machine restarts automatically when the gun is operated, provided that the master switch is on.

### Usage as a cold water high pressure cleaner

- Leave the ignition "OFF". Rocker switch (1A) to "0".
- Start cleaning

### Usage as a hot water high pressure cleaner

 Set the target temperature on the thermostat to min. 40 °C and than switch the ignition "ON" (rocker switch). The oil burner starts to work. The water is heated up and kept at the temperature you have set.

During high-pressure operation (above 30 bars) the temperature may not exceed 90 °C.

### Steam level

To reach the steam level, i.e. over 90 ° C water temperature, adjust the pressure and the water quantity downwards using the handwheel (4) and choose the desired temperature of max. 150 °C with the thermostat. For high pressure cleaners with hose drum applies: The hose must always be fully unwound.

During steam operation the pressure may not exceed 30 bars.

### **Usage with detergents**

- The detergent must have the ph-value 7-9 neutral.
- Wait until the pump has pressed the air out of the lines.
- Put the chemical filter into a container with detergent.
- Open the detergent valve (20). The pump now sucks detergent in and mixes it with the high pressure spray.
- Set the desired concentration of detergent.
- At the end of the working procedure with detergent reset the rotary button to "O".
- When the high pressure cleaner is operated with open chemistry valve without chemicals, the pump sucks in air. Damages caused to the pump as a result are not covered by the guarantee.



Comply with additive manufacturers' instructions (e.g. protective equipment and waste water regulations). Use only additives approved for use with high pressure cleaners. Using other additives impairs the safety of the machine.

In the interest of the environment and to keep expenditure down, we recommend sparing use of detergent. Please observe the recommendations of the detergent manufacturer.

After using detergents, rinse the machine for approx. 2 minutes by pressing the trigger of the spray gun.

### Decommissioning

### **Decommissioning**

- Switch off the master switch (position "0").
- Pull the plug out of the power socket.
- Turn off the water supply.
- Open the gun until the pressure is gone.
- Lock the gun.
- Disconnect the water hose.
- Slacken the connections of the high pressure hose and gun and unscrew the high pressure hose from the machine (appliances without hose drum).

### **Anti-Freeze Protection**

The machine is normally still partially filled with water after work has been completed. It is therefore necessary to take special precautions to protect the machine from frost.

- Completely empty the machine of water
   Disconnect the machine from the water supply and switch off the ignition.

   Switch on the master switch and open the gun. The pump now presses the remaining water out of the heating coil. Do not allow the machine to run for longer than a minute without water.
- Fill the machine with anti-freeze

  If the machine is not in use for lengthy periods of time, it is advisable to pump anti-freeze into the machine, especially in winter. For this purpose, fill the antifreeze agent into the water box and turn on the machine without ignition (rocker switch (16) to "0"). Wait with opened gun, until the agent comes out of the nozzle.

However, the best protection against frost is to keep the machine in a place that is safe from frost.

### **Care and Maintenance**

Care and maintenance is required to keep the machine in good working order, and to allow you to enjoy the machine for as long as possible.



#### **IMPORTANT!!!**

# Always remove the plug before working on the machine! Only use original Kränzle spare parts

#### What to do!

- Weekly, or after approx. 40 hours of operation
- Check the oil level of the high pressure pump. (see page 13)
   If the oil level is too low, add oil until the oil level is between the two markings on the oil measuring rod.
  - Change the oil (see page 19) if it has a grey or whitish appearance. The oil should be disposed of responsibly.
- Check the filter in front of the float valve in the water tank and the fuel filter in front of the solenoid valve. Clean the filters if necessary.
- Yearly, or after approx. 500 hours of operation
- Desulphurise and decarbonize the heating coil.
- Check if the heating coil is calcified (see page 20).
- Check the oil burner and ignition system.
   Clean the oil nozzle, oil filter, solenoid valve and filter, clean and adjust the ignition transformer, ignition cable and ignition electrodes and replace defective parts.
- Change the oil

### Changing the oil

To do this, take the oil drainage hose (1) connected to the oil drain screw, from the inside of the machine and open the red oil filler cap on the top side of the black oil reservoir. Open the cap at the end of the hose. Drain off the oil into an oil pan and dispose of it responsibly. Close the end of the hose. Refill with oil.



### Oil leakage





If oil leaks out, go to the nearest customer service (dealer) immediately. (Environmental damages, transmission damages, loss of guarantee.)

Type of oil: Formula RS of Castrol - Quantity: 1.0 I

### Adjusting ignition electrodes

For a smooth ignition, the setting of the ignition electrode must be controlled regularly.





### **Fuel System**

IYour fuel may contain particles of dirt, or impurities or water may get into the tank during refuelling.

As a safeguard for the fuel pump the appliance is fitted with a fuel filter (c). Check regularly if the filter is soiled and clean it if necessary.

Check the tank for impurities on a regular basis.

Empty the fuel tank using the drainage screw (d) at the bottom of the tank. Clean the tank and the fuel lines carefully. Screw in the drainage screw.



Detergent and dirty fuel must be disposed of responsibly.



### Decalcifying the heating coil

Calcified machines use an unnecessary amount of energy because the water can only be heated slowly and the excess pressure valve feeds a part of the water back into the pump circuit.

### Calcified machines can be recognised by increased pipeline resistance.

Check pipeline resistance by disconnecting the high pressure lance from the gun and switching the machine on. A full jet of water emerges from the gun. The machine must be decalcified if the pressure shown on the manometer is greater than 25 bars.

#### Decalcifiers are caustic!

Observe the instructions for usage and accident prevention. Wear protective clothing to prevent the decalcifying agent from contacting your skin, eyes and clothing (e.g. gloves, safety mask etc.)

Proceed as follows to decalcify the machine:

- Unscrew the high pressure hose from the machine and decalcify it separately.
- Put the detergent suction hose into a container of decalcifying solution.
- Set the dispenser valve to the maximum concentration.
- Switch on the machine.
- Hold the gun in a separate container and press the trigger.
- Wait for about a minute until the decalcifier comes out of the gun (recognisable by its whitish colour).
- Switch off the machine and allow the solution to act for about 15-20 minutes.
- Switch the machine back on and rinse it through with clear water for about 2 minutes.

Now check whether pipeline resistance is back to an acceptable level. Repeat the decalcifying process if the pressure without the high pressure lance is still above 25 bars.

### Rules, directives, inspections

### Inspections performed by Kränzle

- measurement of earth line resistance
- measurement of voltage and current
- inspection of tension consistency with +/- 1530 V
- pressure check of heating coil at 300 bar
- visual and functional check as per the inspection sheet provided
- exhaust fume analysis (see test strips provided)

### Guidelines for liquid sprayers

The machine conforms with the "Guidelines for liquid sprayers". These guidelines are issued by the organisation of trade associations and may be obtained from Carl Heymann-Verlag KG, Luxemburger Str. 49, 50939 Köln. These guidelines specify that this machine is to be inspected by qualified personnel whenever necessary, but no less than once every 12 months. These inspections must be recorded in the inspection log at the end of this manual.

#### Pressure container and steam boiler directives

Kränzle high pressure cleaning equipment conforms to the pressure container and steam boiler directive. No construction approval, notification of licence and takeover inspection are required. The water capacity is less than 10l.

### Duties of owner

The owner is to ensure that all safety-relevant components are in a serviceable condition before the sprayer is used. (e.g., safety valves, hose and electric cables, spray equipment etc).

### Emission control legislation

With stationary installation, the emission levels of the machine must be checked once a year by a qualified organisation or person according to German law. The first inspection must be carried out four weeks after the machine is commissioned. The owner is responsible for having the inspection performed.

# Description of function - Troubleshooting





### **IMPORTANT!!!**

### Always remove the plug before working on the machine!



- 1 Master switch
- 2 Ignition "ON/OFF
- 3 Brief operating instructions
- 4 Thermostat





- 5 Hand wheel for pressure adjustment
- 6 High pressure pump
- 7 Pressure switch black (start solenoid valve)
- 8 Pressure switch red (start pump)
- 9 Safety valve
- 10 Flow controller
- 11 Motor for ventilator and fuel pump
- 12 Solenoid valve (Fuel)
- 13 Fuel pump

- 14 Fuel manometer
- 15 Fuel filter
- 16 Photo cell Flame monitoring
- 17 Ignition transformer
- 18 Thermosensor water
- 19 Excess temperature release
- 20 Ignition electrodes
- 21 Thermosensor exhaust gas

# Description of function - Troubleshooting

### Cold water mode

- 1. Connect to water supply and determine whether the water tank fills up completely and the float valve stops.
- 2. Ignition (2) to OFF.
- 3. Main switch (1) to ON.
- 4. Open high pressure gun. The pump sucks water from the water tank and moves the water through the heating coil to the lance, the pressure is increased.

After you close the gun, press the red pressure switch (8). The 40-Second-Stop system is activated, i.e. after closing the gun, the pump motor is turned off after 40 seconds. When you open the gun the motor starts again.

If the gun stays closed for more than 20 minutes, the safety switch off is activated and the machine is turned off completely, i.e. if you want to use the machine you must first turn it OFF and then ON with the main switch.



#### **ATTENTION!!**

If the pressure is not built up immediately, there is still air in the pump. Open and close the gun repeatedly to press the air from the machine.

### Hot water mode

Start the machine just like in cold water mode and then turn the rocker switch (2) for the burner to ON. Then, turn the rotary switch on the thermostat, (4) located on the front, to the desired temperature (at least 40 °C) in order to activate the burner, i.e., that fuel is injected.

The manometer (14) on the fuel pump shows approx. 10 bars. If this reading is not displayed, check whether

- 1. there is heating oil in the tank
- 2. the motor fuse (11) in the switch box (below the operation panel) has tripped.
- 3. the fuel sieve (15) or the fuel sieve in the pump (13) is dirty.
- 4. the fuel pump does no operate smoothly or is blocked.
- 5. the ventilator jams.

The thermostat grants permission to open the solenoid valve; after opening the gun, the burner starts. The burner starts and heats up the water to the set temperature. The burner switches off as soon as the desired temperature has been reached.

To avoid substantial fluctuations especially with high temperatures the high pressure cleaner is equipped with an after-heating feature, i.e. 13 seconds after the burner was switched off by the thermostat, the burner is restarted and stopped again after 11 seconds.

If the temperature drops again, the burner switches on automatically thus guaranteeing the required constant temperature.

# Description of function - Troubleshooting

The thermostat (4) is controlled via a thermo-sensor (18) mounted at the outlet of the heaiting coil.

In the switchbox (below the operating panel), a fuse (F1) is installed on the board protecting the motor (11) of the fuel pump and the ventilator. If the motor is overloaded the fuse trips. This may happen if the fuse pump is blocked or sluggish - the same applies if the ventilator is blocked or sluggish or in case of an electrical malfunction.

Another fuse (F2) on the board trips, if the ignition transformer (17) is faulty.

There is a thermosensor (21) in the waste gas tube, which controls an excess temperature relay with trigger function (19), i.e. when the exhaust gas temperature in the chimney increases above 230 °C, this relay triggers. To activate it again, you must wait until the combustion unit has cooled down, i.e. approximately 15 minutes. Then, you can press the button under the cover (19) again. The excess temperature relay can trigger when the machine is operated over a longer period in the highest steam level, or when there is lots of soot on the heating coil due to poor combustion, or when the inside of the heating coil is calcified, so that there is no ventilation (cooling).

As further safety function, the burner is also switched off, when the water temperature exceeds 147 °C.

The appliance is equipped with a visual flame monitoring device. A photo cell (16) is installed above the burning chamber, switching off the fuel supply if the flame is extinguished.

To avoid an overheating of the burning chamber a flow indicator (10) is installed in the high pressure system between the high pressure pump (6) and the burning chamber enabling a fuel supply only if water streams through the heating coil at the same time.

### Control board (p. 28-29)

The control board is equipped with two LEDs for trouble shooting.

- L1: illuminated, if the burner has been released but the flame is not burning. If the flame starts burning within 2 seconds, the LED goes out. If the LED does not go out the combustion has to be checked. If the LED is not illuminated at all, the flame sensor has to be checked. Nevertheless the cleaner can be used as a cold water high pressure cleaner even if the burner is switched off.
- L2: permanently illuminated, if the overcurrent release has tripped.
  - blinking, if the fuel flow valve detects only a low quantity of fuel in the tank or if it is defctive.

# **Troubleshooting**



### **IMPORTANT!!!**

### Always remove the plug before working on the machine!

| Malfunction Water supply  | Cause of malfunction / Trouble shooting  |
|---|--|
| Water tank runs over.   | Float valve is dirty. Float valve is defect.   |
| Water tank does not fill completely.  | Float valve is defect Water filter soiled. Check water inlet quantity.   |
| Pump does not suck.   | Valves stick or are dirty. Suction hose leaks. Chemistry valve is open or leaks. Check hose clips (connections). High-pressure nozzle is clogged.  |
| Test: check water and chemical system for tightness.                            | Connect water inlet directly to the pump (2-4 bar pre-pressure).  Disconnect suction lines below the pump.   |
| High-pressure pump Pump makes lots of noise. Operating pressure is not reached. | Pump sucks air. Check suction connections. Check high-pressure nozzle. Check valves. Check O-rings under valves. Check sleeves. Manometer is defect. Unloader: check stainless steel seat and ball. Check seals on the control piston. |
| Water drops from the pump.  | Replace sleeves in the pump. Replace O-rings.  |
| Oil drops from the transmission.  | Check oil seals (replace). Check plunger and plunger guides. Check water supply, since water deficiency or air suction can cause damage to seals and O-rings (chemistry valve leaks?).   |
|   | Worn high pressure nozzle  |
| Pressure is too low   | Stainless steel seat, ball, O-ring in unloader is dirty or defect.   |
|   | Manometer is defect  |


# **Troubleshooting**

| Malfunation   | Course of molfunction / Trouble abouting  |
|---|---|
| Malfunction Machine does not switch off             | Cause of malfunction / Trouble shooting Check return body and O-ring in unloader of the |
|   | valve housing.  |
|   | Check pressure switch (red).  |
| Test: Jumper (red) pressure switch                  | Check micro switch.   |
|   | Check cable connections.  |
| Appliance does not start or                         | Board is defect. Check electricity supply.  |
| Appliance does not start or stopps during operation | Check main switch.  |
| stopps during operation                             | Check cable connections.  |
|   | Check board.  |
|   | Check pressure switch.  |
|   | Switch off by overcurrent release.  |
| Heating (burner)                                    |   |
| Fuel pump/blower operates, but                      | Set water temperature is reached.   |
| burner does not heat.                               | Increase temperature on thermostat with rotary  |
|   | control switch.   |
|   | Open gun, until temperature drops.  |
|   | Fuel tank is empty  |
|   | Fuel tank is empty. Fuel filter is dirty.   |
|   | Fuel nozzle is dirty.   |
|   | Float switch in fuel tank is defect.  |
|   | Discourifical records in defeat   |
| Fuel pump/blower does not                           | Blower/fuel pump motor is defect. Check electrical equipment.                           |
| operate.  | Check electrical equipment.   |
| - Pump makes lots of noise                          | Check fuse in terminal box.   |
| - Fuel operating pressure has not                   | Coupling between burner motor and fuel pump   |
| been reached  | is defect.  |
| Coupling between burner motor                       | Water in fuel tank.   |
| and fuel pump is broken                             | Dirt or rust in the fuel pump.  |
|   | Clean tank.   |
| B   | Replace fuel pump.  |
| Burning   |   |
| Smoke during operation                              | Fuel is dirty.  |
| Smoke after switching off                           | Nozzle or nozzle stock leaks.   |
| onoke after switching on                            | Water in tank.  |


# **Troubleshooting**

| Malfunction Solenoid valve on the fuel pump   | Cause of malfunction / Trouble shoooting Check pressure switch (black). |
|---|---|
| Solenoid valve on the fuel pump does not open | Check pressure switch (black). Solenoid valve is defect or dirty.       |
| Test: Pressure switch (black)                 | Solehold valve is delect of diffy.                                      |
| Bridge in terminal box between                |   |
| terminal 3 +4                                 | Clean filter, clean supply line, clean fuel pump.                       |
| Test: Connect solenoid valve 230              | Setting is wrong.   |
| V externally                                  | Clean fuel nozzle, or replace it.                                       |
| Oil pressure on the fuel pump is too low      |   |
| too high<br>Ignition does not function        |   |
|   | Check ignition cable.   |
|   | Charring of plug-in contacts by moisture.                               |
|   | Cable is broken Check ignition transformer connections.                 |
|   | Transformer is defect   |
|   | Ignition electrode has been falsely set or burnt                        |
| Ventilator does not operate                   | up.   |
|   | Blower-/fuel pump motor is defect.                                      |
|   | Check electrical equipment.   |
|   | Check fuse in terminal box.   |
|   | Coupling between burner motor and fuel pump                             |
| Spray gun -                                   | is defect.  |
| High-pressure hose                            | Check for leakages.   |
| Gun drips                                     | Replace seals.  |
| High pressure hose drips                      | Replace O-ring under screwed connection.                                |
| Nozzle is clogged                             | Manometer indicates pressure, but no water                              |
| Sucking detergent                             | comes out of HP-hose – clean nozzle.                                    |
| Detergent is not sucked                       | Pump sucks air.   |
| J   | Check hose clips.   |
|   | Test:   |
|   | Connect water line to the pump.   |
|   | Water inlet: 2 - 4 bar pre-pressure. No water                           |
|   | must come from the detergent hose.                                      |


# Circuit diagramme 230V / 50Hz



# Circuit diagramme 400V / 50Hz



# **Complete Assembly**




# Kränzle therm C

# Spare parts list KRÄNZLE therm C Complete Assembly

| Š            | Description                   | Ωty.         | Order No. | ŏ    | Description                               | aty.         | Order No.     |
|--------------|-------------------------------|--------------|-----------|------|---|--------------|---------------|
| <b>-</b>     | Fahrgestell                   | _            | 44.800    | 22   | Schraube M6x35 DIN6912                    | 2            | 46.024        |
| 7            | Achse                         | 4            | 44.820    | 23   | Schraube M5x16 DIN7985                    | 4            | 40.178        |
| က            | Rad d250                      | 4            | 46.010    | 24   | Deckel Zuluft                             | _            | 44.801        |
| 4            | Federstecker                  | 4            | 40.115 1  | 25   | Ablassschraube                            | 7            | 44.004 1      |
| 2            | Radkappe                      | 4            | 46.011    | 56   | Dichtung für Ablassschraube               | 7            | 41.047 1      |
| 9            | Schraube M6x30 DIN912         | œ            | 43.037    | 27   | Scheibe 8,4 DIN9021                       | 4            | 41.409        |
| 7            | Wasserkasten                  | _            | 44.805    | 28   | Schraube M8x80 DIN931                     | 4            | 44.832        |
| œ            | Schraube M6x16 DIN912         | က            | 44.831    | 59   | Scheibe Haubenbefestigung                 | 9            | 44.849        |
| 6            | Tankdeckel mit Pos. 10        | _            | 44.833    | 30   | Scheibe DIN9021 8,4                       | 4            | 41.409        |
| 10           | O-Ring 70 x 5                 | <del>-</del> | 44.020    | 31   | Schraube M 8 x 110 DIN931                 | 4            | 44.826        |
| 7            | Brennstofftank                | _            | 44.806    | 32   | Scheibe D40x19x1,5                        | 16           | 46.533        |
| 12           | Haube hinten                  | _            | 44.812    | 33   | Büchse Haubenbefestigung                  | 9            | 44.849 1      |
| 13           | Schraube M5x14 DIN7985        | 9            | 40.536    | 34   | O-Ring 10 x 2,0                           | 9            | 43.068        |
| <del>/</del> | Haube vorn                    | _            | 44.813    | 36.1 | Motor-Pumpe für therm C 11/130            | <del>-</del> | 44.883        |
| 15           | Kaminblende                   | <del>-</del> | 44.825    | 36.2 | Motor-Pumpe für therm C 13/180            | <del>-</del> | 44.884        |
| 16           | Schubbügel                    | _            | 44.834    | 36.3 | Motor-Pumpe für therm C 15/150            | <del>-</del> | 44.885        |
| 17           | Köchertopf                    | _            | 46.503    | 37   | Hochdruckschlauch NW 8 10 m               | _            | 44.878        |
| 9            | Lanzenhalter                  | 7            | 42.610    | 38   | O-Ring 9,3 x 2,4 Viton                    | 7            | 13.273 1      |
| 19           | Lanzenständer                 | _            | 46.502    | 39.1 | M2000-Pistole einteilig mit HD-Düse 25045 | 045          | 12.486-D25045 |
| 20           | Schraube M6x16                | 7            | 40.171 1  |      | (therm C 11/130 + 13/180)                 |              |               |
| 21           | Blechschraube 3,5x9,5 DIN7981 | 80           | 44.161    | 39.2 | M2000-Pistole einteilig mit HD-Duse 25055 | 055          | 12.486-D25055 |
|              |                               |              |           |      | (therm C 15/150)                          |              |               |

# Electronics switchbox




# Kränzle therm C

| RÄNZLE therm C     | switchbox   |
|--------------------|-------------|
| Spare parts list K | Electronics |


| o<br>V | Description                             | aty.         | Order No. | Š.   | Description                           | aty.         | Order No. |
|--------|---|--------------|-----------|------|---------------------------------------|--------------|-----------|
| -      | Elektrokasten                           | _            | 44.807    | 27   | Zugentlastungsschelle                 | _            | 43.431    |
| 2.1    | Deckel für Elektrokasten therm C 11/130 | _            | 44.8082   | 28   | Schraube 3,5 x 14                     | 7            | 44.525    |
| 2.2    | Deckel für Elektrokasten therm C 13/180 | _            | 44.8083   | 59   | Netzanschlussleitung Drehstrom        | _            | 44.036    |
| 2.3    | Deckel für Elektrokasten therm C 15/150 | _            | 44.8084   |      | 8,0m, 4x 1,5 mm², H07RNF              |              |           |
|        | mit Dichtung                            |              |           | 29.1 | Netzanschlussleitung Wechselstrom     | _            | 44.092    |
| က      | Frontplatte Manometer                   | _            | 44.809    |      | 5,75m, 3x 1,5 mm², H07RNF             |              |           |
| 4      | Kabelaufwicklung                        | 7            | 44.822    | 30   | PG16-Verschraubung 1 Durchführung     | 7            | 41.419 1  |
| 2      | Schraube 5 x 25                         | 4            | 41.414 1  | 31   | PG16-Verschraubung 2 Durchführungen   | က            | 44.132    |
| 9      | Bock für Schalter                       | _            | 44.810    | 32   | PG16-Verschraubung 3 Durchführungen   | <del>-</del> | 44.133    |
| 7      | Schraube 5x14                           | 10           | 43.426    | 33   | Manometer                             | _            | 15.039 1  |
| œ      | Bock für Thermostat                     | _            | 44.811    | 34   | Gehäuse Waschmittelventil             | _            | 44.145    |
| 6      | Dichtung für Thermostat                 | _            | 44.818    | 32   | O-Ring 5 x 1,5 (Viton)                | _            | 44.150    |
| 9      | Dichtung für Schalter                   | _            | 44.817    | 36   | O-Ring 28,24 x 2,62                   | <del>-</del> | 44.149    |
| 7      | Schalter                                | 7            | 44.835    | 37   | Regulierkolben Chemieventil           | _            | 44.147    |
| 12     | Drehgriff Thermostat                    | _            | 44.153    | 38   | Edelstahlfeder 1,8 x 15 x 15          | <del>-</del> | 44.148    |
| 13     | Gewindeschneidschraube M 2,5 x 8        | _            | 44.168    | 39   | Deckel für Chemieventil               | _            | 44.146    |
| 4      | Thermostat drehbar elektronisch         | _            | 44.951    | 40   | Blechschraube 3,5 x 16                | 7            | 44.161    |
| 15     | Deckel für Übertemperaturauslöser       | _            | 44.361    | 40.1 | Blechschraube 3,9 x 13                | _            | 41.078    |
| 15.1   | Dichtung für Deckel Übertemp.           | _            | 44.182 1  | 4    | Blechschraube $3.5 \times 19$         | 7            | 44.162    |
| 16     | Steuerplatine Übertemperaturausl. 400V  | _            | 44.370    | 42   | Drehgriff Chemieventil mit Blendkappe | _            | 44.151    |
| 16.1   | Steuerplatine Übertemperaturausl. 230V  | _            | 44.370 1  | 4    | Schraube 5,0 x 20 mit angepr. Scheibe | 10           | 43.018    |
| 17     | Schraube 3,5 x 8                        | က            | 43.430    | 45   | Durchführungstülle für Kapillarrohr   | 7            | 44.823    |
| 18     | Schraube 4,0 x 16                       | œ            | 43.417    | 46   | Dichtung für Deckel Übertemp.         | <del>-</del> | 44.182 1  |
| 19     | Erdungsklemme                           | _            | 44.839    | 47   | Dichtung Elektrokasten                | _            | 44.838    |
| 50     | Feinsicherung M 1,25 A                  | _            | 44.676    | 48   | Klemmbügel für Manometer              | <del>-</del> | 44.049    |
| 20.1   | Feinsicherung M 2,0 A                   | _            | 44.889 1  | 49   | Anschlussmuffe Manometer              | _            | 44.136    |
| 21     | Schraube M4x8 DIN84                     | 7            | 46.604 1  | 20   | Kunststoffschraube 4,0 x 25           | ω            | 43.425    |
| 22     | Steuerplatine 400 V / 50/60 Hz          | _            | 44.836    | 21   | Schlauchklemme 9 - 9                  | 7            | 44.054    |
| 22.1   | Steuerplatine 230 V / 50/60 Hz          | _            | 44.837    | 25   | Schlauch für Waschmittelansaugung     | _            | 44.055    |
| 23     | Schütz 400 V / 50/60 Hz                 | _            | 46.005 1  | 23   | Schlauch mit Filter und Rückschlagv.  | <del>-</del> | 44.056 1  |
| 23.1   | Schütz 230 V / 50/60 Hz                 | _            | 46.005    | 24   | Rückschlagventil für Waschmittelans.  | _            | 44.240 1  |
| 24     | Schraube 4,0 x 25 mit angepr. Scheibe   | 7            | 43.425    | 22   | Druckmessleitung                      | _            | 44.102 1  |
| 25     | Überstromauslöser 9-12,5A               | _            | 42.6412   |      |                                       |              |           |
| 25.1   | Überstromauslöser 11,3-16A              | _            | 42.641    |      | Chemieventil kpl. Pos. 34-42          |              | 44.052    |
| 56     | Kabeltrompete mit Zugentlastung         | <del>-</del> | 44.819    |      |                                       |              |           |

# Water supply and brake



| No. | Description                            | Qty. | Order No.               |
|-----|--|------|-------------------------|
| 1   | Wassertank                             | 1    | 44.805                  |
| 4   | Schwimmerventil                        | 1    | 46.250                  |
| 5   | Moosgummidichtung                      | 1    | 46.261                  |
| 6   | Mutter R3/4"                           | 1    | 46.258                  |
| 7   | Kunststoffschraube 5x14                | 1    | 43.426                  |
| 8   | Scheibe 5,3 DIN9021                    | 1    | 50.152                  |
| 9   | Zugfeder                               | 1    | 46.020                  |
| 10  | Deckel Bremse                          | 1    | 46.016                  |
| 11  | Hebel Bremse                           | 1    | 44.804                  |
| 12  | Zylinderschraube M8 x 20               | 1    | 41.480                  |
| 13  | Innensechskantschraube M4x10           | 4    | 46.002                  |
| 14  | Schelle                                | 2    | 43.431                  |
| 15  | Bolzen für Bremse                      | 1    | 46.018                  |
| 16  | HD-Schlauch Wasserausgang              | 1    | 44.840                  |
| 17  | Haltescheibe                           | 1    | 44.841                  |
| 18  | Ausgangsteil R1/4" x ST30              | 1    | 44.855                  |
| 19  | Schraube DIN912 M5x12                  | 2    | 41.019 4                |
| 20  | Zahnscheibe 5,1                        | 2    | 43.483                  |
| 21  | Bundschraube<br>Brake compl. Pos. 7-15 | 1    | 46.019<br><b>44.880</b> |


# Fuel supply



Fuel pump compl. Pos. 22-26, 28

44.852 1


# Combustion chamber



# Spare parts list KRÄNZLE therm Combustion chamber

|          | Compustion champe                              |       |           |
|----------|--|-------|-----------|
| No.      | Description                                    | Qty.  | Order No. |
| 1        | Gebläsegehäuse                                 | 1     | 44.802    |
| 2        | Schraube M 5 x 10                              | 5     | 43.021    |
| 3        | Schraube 3,9 x 9,5                             | 3     | 41.079    |
| 4        | Haltebock                                      | 1     | 44.395    |
| 5        | Haltesockel Zündkabel                          | 1     | 44.114 2  |
| 8        | Federring A 8                                  | 5     | 44.222    |
| 9        | Edelstahlmutter M 8                            | 2     | 14.127 2  |
| 11       | Brennstoffleitung "Düsenstock" 115 mm          | 1     | 44.089 1  |
| 11.1     | Brennstoffleitung "Düsenstock" 120 mm (C 11/13 | 30) 1 | 44.089    |
| 12       | Winkelverschraubung 6L x 6L                    | 1     | 44.106    |
| 13       | Brennstoffleitung Pumpe                        | 1     | 44.845    |
| 15       | Halterung Zündtrafo mit Pos. 4 und 5           | 1     | 44.821    |
| 17       | Blechschraube 4,8 x 13                         | 1     | 44.112    |
| 18       | Zündtrafo 50 Hz                                | 1     | 44.851    |
| 19       | Schraube 4,0 x 60                              | 4     | 43.420    |
| 20       | Deckel Gebläsegehäuse                          | 1     | 44.803    |
| 21       | Schraube 4,8 x 16                              | 4     | 40.282    |
| 22       | Lüfterrad                                      | 1     | 44.847    |
| 24       | Gebläsemotor 200-240 V / 50/60 Hz, DR rechts   | i     | 44.850 6  |
| 25       | Steckkupplung                                  | i     | 44.852 2  |
| 26       | Brennstoffpumpe kpl.                           | 4     | 44.852 1  |
| 27       | Hochspannungszündkabel                         | 1     | 44.114    |
| 29       | Zyl.schraube mit ISK M 5 x 12 DIN 912          | 1     | 40.134    |
| 30       | Einschraubwinkelverschr. 3/8" x 12L            | 2     | 44.092    |
| 31       | Fächerscheibe 4.3                              | 4     | 43.471    |
| 32       | Schraube M 4 x 10                              | 4     | 43.470    |
| 33       | Gewindestift M 6 x 8 DIN 914                   | 1     | 44.090    |
| 34       | L-Verschraubung                                | 1     | 44.869    |
| 35       | Temperaturfühler                               | 1     | 44.954    |
| 36       | Ermetomutter 12 mm                             | 1     | 40.075    |
| 37       | O-Ring 14 x 2                                  | 1     | 43.445    |
| 38       | Ermetorohr 12x85 mit 2x M12 x 1                | 1     | 44.848 1  |
| 39       | Druckfeder Strömungswächter                    | 1     | 14.217    |
| 39<br>40 | Anschlagstopfen mit Zapfen Strömungswächter    | 1     | 14.217    |
| 40       | 0 1 1  | 1     |           |
|          | Strömungswächter kpl.                          | 1     | 12.610    |
| 42       | Strömungskörper mit Zapfen für Feder           | 1     | 14.218    |
| 43       | Abdeckung                                      | 4     | 12.603    |
| 44       | Schraube M 4 x 8                               |       | 44.216    |
| 45       | Eingangsteil M18x1,5" x 12L                    | 1     | 44.364    |
| 46       | Magnetschalter                                 | 1     | 40.594 2  |
| 47       | Schlauchführung                                | 1     | 44.830    |
| 48       | Schraube M 5 x 14                              | 2     | 40.536    |
| 49       | Strömungskörper incl. Stopfen und Feder        | 1     | 14.218 1  |
| 50       | Hochdruckschlauch Wasserausgang                | 1     | 44.840    |
| 51       | Abschlussring                                  | 2     | 44.086    |
| 52       | Gewindestift M 6 x 8 DIN 914                   | 2     | 44.090    |
| 54       | Übertemperatur-Fühler                          | 1     | 44.388 1  |
| 55       | Mutter   | 1     | 44.172    |
| 56       | Überwurfmutter                                 | 4     | 12.636    |
| 57       | Nippel   | 4     | 12.637    |
| 58       | O-Ring 9,5 x 2                                 | 4     | 12.635    |
| 60       | Gebläse-Brennstoffpumpeneinheit Pos. 20-26, 2  | 9-33  | 44.882    |


### Combustion chamber



# Spare parts list KRÄNZLE therm Combustion chamber

| No. | Description                                     | Qty. | Order No. |
|-----|---|------|-----------|
| 1   | Außenmantel mit Zugbolzen                       | 1    | 44.860    |
| 3   | Innenmantel mit Bodenplatte                     | 1    | 44.064 1  |
| 4   | Deckel Düsenstock                               | 1    | 44.079    |
| 5   | Innendeckel mit Kamin und Flammrohr             | 1    | 44.861 1  |
| 6   | Außendeckel                                     | 1    | 44.862    |
| 7   | Brennstoffdüse 60° B 1,35 gph (C11/130)         | 1    | 44.077 2  |
| 7.1 | Brennstoffdüse 60° B 1,5 gph (C13/180; C15/150) | 1    | 44.077    |
| 8   | Blockelektrode                                  | 1    | 44.854    |
| 9   | Düsenstock Ø 25 mm, 6 Schl.                     | 1    | 44.076 4  |
| 10  | Düsenhalter                                     | 1    | 44.078    |
| 11  | Edelstahlschraube M 6 x 10                      | 3    | 44.177    |
| 12  | Klemmblech für Elektrode                        | 1    | 44.076 1  |
| 13  | Zyl.schraube mit ISK M 5 x 15 DIN6912           | 1    | 44.076 2  |
| 15  | Abschlusshülse                                  | 2    | 44.081    |
| 16  | Schraube M 6 x 12 DIN 933                       | 2    | 44.090 1  |
| 19  | Edelstahlmutter M 8                             | 7    | 14.127 2  |
| 20  | Federring A 8                                   | 7    | 44.222    |
| 21  | Flammsensor optisch                             | 1    | 44.256 1  |
| 22  | Schraube M 4 x 12 DIN7985                       | 4    | 41.489    |
| 25  | Heizschlange                                    | 1    | 44.900    |
| 27  | Isolationsplatte                                | 1    | 44.360    |
| 28  | Zugbolzen                                       | 10   | 44.863    |
| 29  | Spannstift 4 x 14                               | 10   | 44.829    |
| 30  | Zahnscheibe 4,3                                 | 10   | 43.471    |
| 31  | Schraube DIN912 M 4 x 10                        | 10   | 46.002    |


## Unloader and pressure switch



| No. | Description                                      | Qty. | Order No. |
|-----|--|------|-----------|
| 80  | Steuerkolben kpl.                                |      | 40.490    |
| 81  | Ausgangsstück für Schalter rot kpl.              |      | 15.009 3  |
| 82  | Druckschalter (rot) kpl.<br>Mit Kabel 1,10 m     |      | 44.895 1  |
| 83  | Ventilgehäuse kpl.                               |      | 44.320    |
| 84  | Druckschalter (schwarz) kpl.<br>Mit Kabel 1,10 m |      | 44.895    |
| 85  | Ausgangsstück für Schalter schwarz kpl.          |      | 15.011 1  |

| No.            | Description                                       | Qty.   | Order No.          |
|----------------|---|--------|--------------------|
| 5              | O-Ring 16 x 2                                     | 1      | 13.150             |
| 5.1            | O-Ring 13,94 x 2,62                               | 1      | 42.167             |
| 8              | O-Ring  | 1      | 12.256             |
| 9              | Edelstahlsitz                                     | 1      | 14.118             |
| 10             | Sicherungsring                                    | 1      | 13.147             |
| 11             | Edelstahlkugel 8,5 mm                             | 1<br>1 | 13.148             |
| 12<br>13       | Edelstahlfeder<br>Verschlussschraube              | 1      | 14.119<br>14.113   |
| 14             | Steuerkolben                                      | 1      | 14.113             |
| 15             | Parbaks 16 mm                                     | 1      | 13.159             |
| 16             | Parbaks 8 mm                                      | 1      | 14.123             |
| 17             | Spannstift  | i      | 14.148             |
| 18             | Kolbenführung spezial                             | i      | 42.105             |
| 19             | Mutter M 8 x 1                                    | ż      | 14.144             |
| 20             | Ventilfeder schwarz                               | 1      | 14.125             |
| 21             | Federdruckscheibe                                 | 1      | 14.126             |
| 22             | Nadellager  | 1      | 14.146             |
| 23             | Handrad   | 1      | 40.457             |
| 24             | Kappe Handrad                                     | 1      | 40.458             |
| 25             | Elastic-Stop-Mutter                               | 1      | 14.152             |
| 26             | Parbaks 7 mm                                      | 1      | 15.013             |
| 27             | Ventilstopfen mit Druckstück                      | 1      | 42.106             |
| 49             | O-Ring 3,3 x 2,4                                  | 1      | 12.136             |
| 50             | O-Ring 5 x 1,5                                    | 1      | 15.014             |
| 51             | Führungsteil Steuerstößel                         | 1      | 15.009 1           |
| 52             | O-Ring 13 x 2,6                                   | 2<br>1 | 15.017             |
| 53<br>54       | O-Ring 14 x 2                                     | 1<br>3 | 43.445             |
| 54<br>55       | Parbaks 4 mm<br>Stützscheibe dm 5                 | 3<br>1 | 12.136 2<br>15.015 |
| 55.1           | Stützscheibe dm 4                                 | 2      | 15.015             |
| 56             | Edelstahlfeder                                    | 1      | 15.016             |
| 57             | Steuerstößel lang                                 | i      | 15.010 2           |
| 58             | Parbaks   | i      | 15.013             |
| 59             | Stopfen M10x1 (durchgebohrt)                      | i      | 13.385 1           |
| 60             | Gehäuse Elektroschalter (schwarz)                 | 1      | 15.007             |
| 60.1           | Gehäuse Elektroschalter (rot)                     | 1      | 15.007 1           |
| 61             | Gummimanschette PG 9 ` ´                          | 1      | 15.020             |
| 62             | Scheibe PG 9                                      | 1      | 15.021             |
| 63             | Verschraubung PG 9                                | 1      | 15.022             |
| 64             | Kabel 2 x 1,0 mm <sup>2</sup> 1,10 m grau         | 1      | 44.871             |
| 64.1           | Kabel 2 x 1,0 mm <sup>2</sup> 1,10 m schwarz      | 1      | 44.235             |
| 65             | Blechschraube 2,9 x 16                            | 6      | 15.024             |
| 66             | Deckel Elektroschalter (schwarz)                  | 1      | 15.008             |
| 66.1           | Deckel Elektroschalter (rot)                      | 1      | 15.008 1           |
| 67             | O-Ring 44 x 2,5                                   | 1<br>1 | 15.023             |
| 68             | Mikroschalter                                     | 2      | 44.262             |
| 69<br>70       | Zylinderschraube M 4 x 20<br>Sechskant-Mutter M 4 | 2      | 15.025<br>15.026   |
| 70<br>72       | Druckfeder 1 x 8.6 x 30                           | 1      | 40.520             |
| 73             | Grundteil Elektroschalter                         | 1      | 15.009             |
| 74             | Steuerkolben                                      | i      | 15.010             |
| 7 <del>5</del> | Aluminium-Dichtring                               | 2      | 13.275 1           |
| . •            |   | _      |                    |

## Safety valve for heating coil




| No. | Description                         | Qty. | Order No |
|-----|-------------------------------------|------|----------|
| 1   | Ventilkörper                        | 1    | 14.145   |
| 4   | Ermetoverschraubung R 3/8" x 12 mm  | 1    | 40.076   |
| 5   | Ermetowinkel R 1/4" x 12 mm         | 1    | 44.864   |
| 6   | Ermetowinkel 12 mm x 12 mm Mutter   | 1    | 44.865   |
| 7   | Stopfen R1/4"                       | 1    | 13.387   |
| 8   | Dichtring Aluminium                 | 1    | 13.275 1 |
| 10  | Spanstift                           | 1    | 14.148   |
| 11  | Steuerkolben                        | 1    | 14.110   |
| 12  | O-Ring 16 x 2                       | 2    | 13.150   |
| 13  | Kolbenführung                       | 1    | 14.109   |
| 14  | Parbaks 16 mm                       | 1    | 13.159   |
| 15  | Parbaks 8 mm                        | 1    | 14.123   |
| 17  | Anschlussmuffe für Hydrospeicher    | 1    | 44.140 1 |
| 18  | Hydrospeicher                       | 1    | 44.140   |
| 21  | Ventilfeder                         | 1    | 14.125   |
| 22  | Federdruckscheibe                   | 1    | 14.126   |
| 23  | Sechskantmutter M8                  | 2    | 14.127   |
| 33  | Rücklaufschlauch S200               | 1    | 44.867   |
| 34  | Einschraubwinkel                    | 1    | 40.121   |
| 35  | O-Ring 11 x 1,44                    | 1    | 12.256   |
| 36  | Edelstahlsitz                       | 1    | 14.118   |
| 37  | Sprengring                          | 1    | 13.147   |
| 38  | Edelstahlkugel 10 mm                | 1    | 12.122   |
| 39  | Edelstahlfeder                      | 1    | 14.119   |
| 40  | O-Ring 13,94 x 2,62                 | 1    | 42.167   |
| 41  | Eingangsstück M20x1,5" x R1/4"      | 1    | 13.136 1 |
| 42  | Anschlussteil Druckmessleitung      | 1    | 44.868   |
| 43  | Verbindungsschlauch S200-Strömungw. | 1    | 44.093 2 |
|     | Steuerkolben kpl. Pos. 10-15; 21-23 |      | 14.110 1 |

44.888

Sicherheitsventli kpl. Pos. 1-15; 21-42


# Valve housing



| No. | Description  | Qty.             | Order No. |
|-----|--|------------------|-----------|
| 1   | Ventilgehäuse AM-Pumpe                                       | 1                | 40.451 1  |
| 2   | O-Ring 15 x 2  | 6                | 41.716    |
| 3   | Ventile (grün) für APG-Pumpe                                 | 6                | 41.715 1  |
| 4   | O-Ring 16 x 2  | 6                | 13.150    |
| 5   | Ventilstopfen  | 5                | 41.714    |
| 5.1 | Ventilstopfen mit Druckteil                                  | 1                | 42.106    |
| 7   | Innensechskantschraube M10 x 35                              | 4                | 42.509 1  |
| 8   | Ansaugschlauch mit Nippel R1/4"                              | 2                | 44.096 4  |
| 9   | Saugzapfen Schlauchanschluss                                 | 1                | 13.236    |
| 10  | Wasserfilter   | 2                | 42.633    |
| 11  | Dichtring  | 1                | 40.019    |
| 12  | Stopfen 3/8"   | 1                | 40.018    |
| 13  | Manschette 18 x 26 x 4/2                                     | 3                | 41.013    |
| 14  | Backring 18 mm   | 6                | 41.014    |
| 15  | O-Ring   |                  | 40.026    |
| 16  | Leckagering 18 mm  | 3<br>3<br>3<br>3 | 41.066    |
| 18  | Gewebemanschette 18 x 26 x 5,5/3                             | 3                | 41.013 1  |
| 20  | Zwischenring 18 mm   | 3                | 41.015 2  |
| 23  | Druckring  | 3                | 41.018    |
| 25  | O-Ring 11 x 1,5  | 1                | 12.256    |
| 26  | Edelstahlsitz Ø 7  | 1                | 14.118    |
| 27  | Sprengring   | 1                | 13.147    |
| 28  | Ausgangsteil Pumpe R1/4" x 12                                | 1                | 44.897    |
| 29  | Kupferring   | 1                | 42.104    |
| 30  | Dichtstopfen R1/4" mit Bund                                  | 1                | 42.103    |
| 32  | Dichtstopfen M 8 x 1   | 2                | 13.158    |
| 33  | Ausgangsteil   | 1                | 40.522    |
| 34  | Edelstahlkugel Ø10   | 1                | 12.122    |
| 35  | Rückschlagfeder "K"  | 1                | 14.120 1  |
| 37  | O-Ring 18 x 2  | 1                | 43.446    |
|     | Valve housing compl.   |                  | 44.320    |
|     | Repkit valves for APG-pump                                   |                  | 41.748 1  |
|     | 6x Pos. 2; 6x Pos. 3; 6x Pos. 4                              |                  | 7111791   |
|     | Repair kit sleeves 18 mm                                     |                  | 41.049 1  |
|     | 3x Pos. 13; 6x Pos. 14; 3x Pos. 15; 3x Pos.                  | 23: 3x Pos. 18   | 711073 1  |
|     | 3x 1 03. 10, 0x 1 03. 1 <del>4</del> , 3x 1 03. 13, 3x 1 03. | 20, 00 1 03. 10  |           |

43


# **Pump**



# Spare parts list KRÄNZLE therm C Pump


| No.  | Description                                 | Qty. | Order No.    |
|------|---|------|--------------|
| 1    | Ölgehäuse mit Öldichtungen                  | 1    | 40.452       |
| 4    | Innensechskantschraube M 8 x 25             | 6    | 40.053       |
| 5    | Sicherungsscheibe                           | 6    | 40.054       |
| 6    | Flachdichtung                               | 1    | 40.511       |
| 7    | Öldichtung 18 x 28 x 7                      | 3    | 41.031       |
| 8    | Wellenscheibe                               | 1    | 40.043       |
| 9    | Axial-Rollenkäfig                           | 1    | 40.040       |
| 10   | AS-Scheibe                                  | 1    | 40.041       |
| 11   | Taumelscheibe 9,0° (C 11/130)               | 1    | 40.460-9,0   |
| 11.1 | Taumelscheibe 11,25° (C 13/180)             | 1    | 40.460-11,25 |
| 11.2 | Taumelscheibe 12,0° (C 15/150)              | 1    | 40.460-12,0  |
| 12   | Plungerfeder                                | 3    | 40.453       |
| 13   | Federdruckscheibe                           | 3    | 40.454       |
| 14   | Plunger 18mm (AM-Pumpe)                     | 3    | 40.455       |
| 15   | Sprengring                                  | 3    | 41.035       |
| 16   | O-Ring 14 x 2                               | 2    | 43.445       |
| 17   | Verschlussschraube M 18 x 1,5               | 1    | 41.011       |
| 18   | Flachdichtung                               | 1    | 41.019 3     |
| 19   | Deckel                                      | 1    | 40.518       |
| 20   | Innensechskantschraube M 5 x 12             | 4    | 41.019 4     |
| 21   | Ölmessstab (AM-Pumpe)                       | 1    | 40.461       |
| 23   | Ölablassschlauch                            | 1    | 44.128 1     |
| 24   | Kupferring                                  | 3    | 14.149       |
| 25   | Verschlusskappe                             | 1    | 44.130       |
|      | Oil housing AM compl.<br>Pos. 1, 4-7, 12-17 |      | 40.452 1     |

# Pump motor



| No. | Description  | Qty. | Order No.        |
|-----|--|------|------------------|
| 1.1 | Stator BG100 2,3kW 230V / 50Hz   | 1    | 40.720           |
| 1.2 | Stator BG100 4,8 kW 400V / 50Hz  | 1    | 40.710           |
| 2   | A-Lager Flansch  | 1    | 40.700           |
| 3.1 | Rotor BG100 230V / 50Hz  | 1    | 40.703 1         |
| 3.2 | Rotor BG100 400V / 50Hz  | 1    | 40.703           |
| 4   | Lüfterrad BG100  | 1    | 40.702           |
| 5   | Lüfterhaube BG 100   | 1    | 40.701           |
| 10  | Schrägkugellager 7306  | 1    | 40.704           |
| 11  | Öldichtung 35 x 47 x 7   | 1    | 40.080           |
| 12  | Passfeder 8 x 7 x 28   | 1    | 40.459           |
| 13  | Kugellager 6206 - 2Z   | 1    | 40.538           |
| 14  | Innensechskantschraube M 6 x 30  | 4    | 43.037           |
| 19  | Schraube M 4 x 12  | 4    | 41.489           |
| 20  | Schelle für Lüfterrad BG100  | 2    | 40.535           |
| 22  | Erdungsschraube kpl.   | 1    | 43.038           |
|     | Motor compl. 2.3 kW 230V / 50Hz<br>Motor compl. 4.8 kW, 3~ 400V / 50Hz |      | 24.085<br>24.080 |


# Terminal box



| No. | Description  | Qty. | Order No.        |
|-----|--|------|------------------|
| 1   | Klemmkasten  | 1    | 44.814           |
| 2   | Deckel Klemmkasten   | 1    | 44.815           |
| 3   | Dichtung Deckel  | 1    | 44.816           |
| 4   | Schraube 5,0 x 14  | 3    | 43.426           |
| 5   | Kunststoffschraube 3,5 x 20  | 2    | 43.415           |
| 6   | Lüsterklemme 5-pol.  | 1    | 43.326 1         |
| 7   | PG9-Verschraubung (C 13/180; C 15/150)   | 1    | 43.034           |
| 7.1 | PG9-Verschlusstopfen (C 11/130)  | 1    | 44.142           |
| 8   | PG9-Gegenmutter  | 1    | 41.087 1         |
| 9   | PG16-Verschraubung   | 1    | 41.419 1         |
| 10  | PG16-Gegenmutter   | 1    | 44.119           |
| 11  | Kondensator 70 μF  | 1    | 43.322           |
| 12  | Flachdichtung  | 1    | 43.030           |
| 13  | Schraube M 4 x 12  | 4    | 41.489           |
|     | Terminal box compl. 2.3 kW 230V / 50Hz<br>Terminal box compl. 4.8 kW, 3~ 400V / 50Hz | ,    | 44.886<br>44.887 |

### Hose drum


# (Special accessory) Upgrade kit: 44.152 2



# Spare parts list KRÄNZLE therm Hose drum


| Ö        | Description                    | Qty.         | Order No. | o<br>N | Description                   | Qty. | Order No. |
|----------|--------------------------------|--------------|-----------|--------|-------------------------------|------|-----------|
| _        | Seitenschale Schlauchführung   | -            | 40.302    | 35     | Haltebügel                    | 1    | 44.143    |
| 7        | Seitenschale Wasserführung     | _            | 40.301    | 36     | Gummistopfen                  | 7    | 40.208 1  |
| က        | Trommel Unterteil              | _            | 40.304    | 37     | Schloßschraube M8 x 35        | 7    | 41.408    |
| 4        | Trommel Oberteil               | _            | 40.303    | 38     | Elastic-Stop-Mutter M 8       | 7    | 41.410    |
| 2        | Innensechskantschraube M4 x 25 | 4            | 40.313    | 40     | Überwurfmutter                | _    | 13.276 2  |
| 9        | Lagerklotz mit Bremse          | _            | 40.306    | 42     | O-Ring 9,3 x 2,4              | 4    | 13.273    |
| 7        | Lagerklotz links               | _            | 40.305    | 44     | Verbindungsschlauch NW 8 1 m  | _    | 44.160    |
| œ        | Klemmstück                     | 7            | 40.307    | 45     | Hochdruckschlauch NW 8 15 m   | _    | 44.879    |
| <b>о</b> | Kunststoffschraube 5,0 x 20    | 12           | 43.018    |        |                               |      |           |
| 10       | Antriebswelle                  | _            | 40.310    |        | Hose drum compl.              |      | 41.259    |
| =        | Welle Wasserführung            | _            | 40.311    |        | without hose, without bracket |      |           |
| 12       | Elastic-Stop-Mutter M 4        | 4            | 40.111    |        |                               |      |           |
| 13       | Handkurbel klappbar            | _            | 40.3200   |        | Bracket compl.                |      | 44.143 1  |
| 4        | Verriegelungsbolzen            | _            | 40.312    |        | consisting of: Pos. 35 - 38   |      |           |
| 15       | Scheibe MS 16 x 24 x 2         | <del>-</del> | 40.181    |        |                               |      |           |
| 16       | Wellensicherungsring 22 mm     | 7            | 40.117    |        |                               |      |           |
| 17       | Wellensicherungsring 16 mm     | _            | 40.182    |        |                               |      |           |
| 8        | Unterlegscheibe Ø 6,4          | <del>-</del> | 50.189    |        |                               |      |           |
| 70       | Parbaks 16 mm                  | 7            | 13.159    |        |                               |      |           |
| 7        | Sicherungsscheibe 6 DIN6799    | <del>-</del> | 40.315    |        |                               |      |           |
| 22       | Schraube M5 x 10               | <del>-</del> | 43.021    |        |                               |      |           |
| 23       | Drehgelenk                     | _            | 40.167    |        |                               |      |           |
| 22       | Distanzring                    | <del>-</del> | 40.316    |        |                               |      |           |
| 27       | O-Ring 6,86 x 1,78             | <del>-</del> | 40.585    |        |                               |      |           |
| 28       | Anschlußstück                  | <del>-</del> | 40.308    |        |                               |      |           |
| 33       | O-Ring 6 x 1,5                 | <del>-</del> | 13.386    |        |                               |      |           |
| 34       | Stopfen M 10 x 1               | _            | 13.385    |        |                               |      |           |

## Gun




| No.  | Description   | Qty. | Order No.     |
|------|---|------|---------------|
| 1    | Pistolenschale re+li  | 1    | 12.450        |
| 2    | Schraube 3,5 x 14   | 10   | 44.525        |
| 3    | Reparatursatz M2000   |      | 12.454        |
| 4    | M2000 Grundbaugruppe  | 1    | 12.458        |
| 18   | Rohr 950 mm; bds. R1/4"   | 1    | 15.004 4      |
| 19   | Abschlussring   | 1    | 12.457        |
| 21   | Aluminium Dichtring 2mm   | 2    | 13.275 1      |
| 22   | Düsenschutz   | 1    | 26.002        |
| 23   | Flachstrahldüse 25045<br>(C 11/130; C 13/180)                             | 1    | D25045        |
| 23.1 | Flachstrahldüse 25055 (C 15/150)  | 1    | D25055        |
|      | M2000-Pistole einteilig mit Düsenscl<br>und HD-Düse 25045 (C 11/130; C 13 |      | 12.486-D25045 |
|      | <b>M2000-Pistole</b> einteilig mit Düsenschund HD-Düse 25055 (C 15/150)   | nutz | 12.486-D25055 |

## Water intake filter



| No. | Description                    | Qty. | Order No. |
|-----|--------------------------------|------|-----------|
| 1   | Filtergrundkörper              | 1    | 13.308    |
| 2   | Filterbecher                   | 1    | 13.302    |
| 3   | Siebkörper                     | 1    | 13.304    |
| 4   | O-Ring 40 x 3,5                | 1    | 13.303    |
| 8   | O-Ring 14 x 2                  | 1    | 43.445    |
| 9   | Tülle                          | 1    | 13.307    |
| 10  | O-Ring 13 x 2,6                | 1    | 13.272    |
| 11  | Überwurfmutter                 | 1    | 41.047 5  |
|     | Filter komplett<br>Pos. 1 - 11 |      | 13.310    |

### Pipeline plan



- 1 Float valve, water inlet
- 2 Water tank
- 3 Control valve, detergent
- 4 High pressure pump with integrated unloader valve
- 5 Pressure switch Motor Start/Stop
- Pressure switch Burner release
- 7 Safety valve for heating coile
- 8 Flow controller
- 9 Fuel pump with solenoid valve
- 10 Fuel filter
- 11 Fuel tank

### Guarantee

#### Guarantee

The guarantee is only valid for material and manufacturing errors. Wearing does not fall within this gurantee.

The instructions in our operating manual must be complied with. The operating instructions form part of the guarantee. The Guarantee is void if other parts are used than genuine Kränzle accessory parts or genuine Kränzle spare parts.

For high-pressure cleaners sold to the user the guarantee period is 24 month.

For high-pressure cleaners sold for industrial use the guarantee period is 12 month. In the case of a guarantee please contact your dealer or authorized seller delivering accessories and your purchase receipt. You can find them in the internet under <a href="https://www.kraenzle.com">www.kraenzle.com</a>.

The guarantee is also void if the machine is used with exceeding the temperature and speed limits, a voltage below the required rating, with less than the required amount of water or with dirty water. Pressure gauge, nozzle, valves, sleeves, high pressure hose and spray equipment are wear parts and are not covered by the warranty.

### Notes



### **High-pressure-cleaners** Hochdruckreiniger Nettoyeurs À Haute Pression





Elpke 97 . 33605 Bielefeld

### **EC** declaration of conformity

Kränzle therm C 11/130 We hereby declare, Kränzle therm C 13/180 that the high-pressure models: Kränzle therm C 15/150

(techn. documentation available from): Manfred Bauer, Fa. Josef Kränzle

Rudolf-Diesel-Str. 20, 89257 Illertissen

K therm C 11/130: 660 I/h Nominal flow

> K therm C 13/180: 780 l/h K therm C 15/150: 900 l/h

comply with the following guidelines and specifications and their amendments for high-pressure cleaners:

Machine guideline 2006/42/EEC Specification for electromagnetic compatibility 2004/108EEC

Outdoor noise directive 2005/88/EC, Art. 13, High-pressure water jet machines

Appendix 3, part B, chapter 27

Sound power level measured: C 11/130: 88 dB (A); C 13/180: 91 dB (A);

C 15/150: 90 dB (A)

C 11/130: 90 dB (A); C 13/180: 93 dB (A) guaranteed:

C 15/150: 92 dB (A)

Applied conformity evaluation

procedures

annex V, noise directive 2005/88/EC

Applied specifications and

standards:

EN 60 335-2-79 :2009 EN 55 014-1 :2006 EN 55 014-2 / A2:2008 EN 61 000-3-2: 2006

EN 61 000-3-3: 2008

Bielefeld, den 29.02.12

Kränzle Josef (Managing Director)

# Inspection sheet

| Customer                                     |  |
|--|--|
|  |  |
|  |  |
|  |  |
|  |  |
|  |  |
|  |  |
| All lines connected                          |  |
| Hose clamps tight                            |  |
| Screws all installed and tightened           |  |
| Ignition cable plugged in                    |  |
| Visual check carried out                     |  |
| Brake function checked                       |  |
| Leak test                                    |  |
| Water tank filled and checked                |  |
| Water inlet checked for tightness            |  |
| Float valve function checked                 |  |
| Machine checked for tightness under pressure |  |
| Electrical check                             |  |
| Earth line checked                           |  |
| Current intake                               |  |
| Carroni intako                               |  |
|  |  |
|  |  |
| Operating pressure                           |  |
| Switch-off pressure                          |  |
|  |  |
|  |  |

### Kränzle therm C \_\_\_\_\_

# Result of flue gas analysis Steam phase checked Chemical valve checked Start/Stop automatic and re-run delay checked Fuel shortage switch checked Thermostat function checked Burner function checked Water inlet temperature 10 11 12 13 14 15 Water temperature reached 72 74 76 78 80 82 84 86 88 90 Fuel pressure 11,5 12 12,5 13 13,5 14 Measured smoke spot number 2 3 Safety equipment sealed with lacquer The appliance fulfills all requirements according to this inspection sheet Name of inspector

Date

Signature

### Inspection report for HP cleaners

Inspection report on annually carried out Labour Safety Inspection (UVV) according to the Guidelines for Liquid Spray Equipment. (This inspection sheet serves as proof for the completion of the retest and must be kept carefully!) Kränzle-Test Stamp Mark: Order Number UVV200106 Owner: Type **therm**: Address: Serial no.: Rep.-order-no.: Scope of inspection: ok repaired yes no Type plate (on hand) Operating manual (on hand) Protective covering, -device Pressure line (tightness) Pressure gauge (function) Float valve (tightness) Spraying device (marking) HP-hose/ connector (damage, marking) Safety valve opens at 10% / 20% excess Pressure reservoir Heating oil line (tightness) Solenoid valve (function) Thermostat (function) Flow controller (function) Power cable (damage) Power plug (damage) Protective conductor (connected) Emergency Off Switch (function) On/Off-switch Water quantity safety device (function) Used chemicals Allowed chemicals determ, value Inspection data set value High-pressure nozzle Operating pressure .....bar Cutting-off pressure.....bar Smoke spot number.....acc. to Bacharach scale CO2-value.....% CO2 Efficiency rating.....% Conductor resist, not exceeded / value: Insulation Leakage current: Gun locked Inspection result (tick) The appliance was checked by an expert according to the Guidelines for Liquid Spray Equipment, the defects found have been rectified so that the Labour Safety can be confirmed. The appliance was checked by an expert according to the Guidelines for Liquid Spray Equipment. The Labour Safety cannot be confirmed unless the defects found are rectified by repair or replacement of the faulty parts. The next retest according to the Guidelines for Liquid Spray Equipment has to be carried out by: Month \_\_\_\_\_Year 

### Inspection report for HP cleaners

Inspection report on annually carried out Labour Safety Inspection (UVV) according to the Guidelines for Liquid Spray Equipment. (This inspection sheet serves as proof for the completion of the retest and must be kept carefully!) Kränzle-Test Stamp Mark: Order Number UVV200106

| Owner: Address:  | Type <b>therm</b> :<br>Serial no.:                       |   |   |  |
|--|--|---|---|--|
|  | Reporder-no.:  |   |   |  |
| Scope of inspection: ok  | yes  | no  | repaired  |  |
| Type plate (on hand)   |  |   |   |  |
| Operating manual (on hand)   |  |   |   |  |
| Protective covering, -device   |  |   |   |  |
| Pressure line (tightness)  |  |   |   |  |
| Pressure gauge (function)  |  |   |   |  |
| Float valve (tightness)  |  |   |   |  |
| Spraying device (marking)  |  |   |   |  |
| HP-hose/ connector (damage, marking)   |  |   |   |  |
| Safety valve opens at 10% / 20% excess   |  |   |   |  |
| Pressure reservoir   |  |   |   |  |
| Heating oil line (tightness)   |  |   |   |  |
| Solenoid valve (function)  |  |   |   |  |
| Thermostat (function)  |  |   |   |  |
| Flow controller (function)   |  |   |   |  |
| Power cable (damage)   |  |   |   |  |
| Power plug (damage)  |  |   |   |  |
| Protective conductor (connected)   |  |   |   |  |
| Emergency Off Switch (function)  |  |   |   |  |
| On/Off-switch  |  |   |   |  |
| Water quantity safety device (function)  |  |   |   |  |
| Used chemicals   |  |   |   |  |
| Allowed chemicals  |  |   |   |  |
| Inspection data  | detern   | n. value  | set value   |  |
| High-pressure nozzle   |  |   |   |  |
| Operating pressurebar  |  |   |   |  |
| Cutting-off pressurebar  |  |   |   |  |
| Smoke spot numberacc. to Bacharach scale   |  |   |   |  |
| CO²-value% CO²   |  |   |   |  |
| Efficiency rating%   |  |   |   |  |
| Conductor resist. not exceeded / value:  |  |   |   |  |
| Insulation   |  |   |   |  |
| Leakage current:   |  |   |   |  |
| Gun locked   |  |   |   |  |
| Inspection result (tick)  The appliance was checked by an expert accor Equipment, the defects found have been rectified. The appliance was checked by an expert accor Equipment. The Labour Safety cannot be confir repair or replacement of the faulty parts. The next retest according to the Guidelines for by: Month | ed so that the ding to the G med unless the Liquid Spray | Labour Safe<br>uidelines for<br>ne defects for<br>Equipment | ty can be confirmed.<br>Liquid Spray<br>und are rectified by<br>has to be carried out |  |
| Place, Date  | Signature .  |   |   |  |



### I. Kränzle GmbH

Elpke 97

D - 33605 Bielefeld

Reprint only allowed with the authorization of Kränzle

■ Made

As date of 06/10/2014

■ in

Germany